

## Sub Subdivision of Township 3 North Range 35 East.

Chains	Set temp Cors. at 20, 40 and 60 chains. And at	
79.40	Intersect E. bdy. 50 lks. S. of $\frac{1}{4}$ Sec. cor. Thence S. $89^{\circ} 39'$ W. on true line.	
19.85	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground, marked 1/16 S <sub>2</sub> on N. face.	
39.70	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.	
59.55	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.	
79.40	To point of beginning. Land rolling. Soil 1st rate.	
	East on random through N. $\frac{1}{2}$ of Sec. 14. Va. $20^{\circ}$ East. Commencing at 1/16 Sec. cor. 20 chains. N. of $\frac{1}{4}$ Sec. cor. bet. Secs. 14 & 15 Set temp. cors. 20, 40 & 60 chains And at	
79.60	Intersect E. bdy. 25 lks. S. of 1/16 Sec. cor. Thence S. $89^{\circ} 49'$ W. on true line.	
19.90	Set basalt stone 16x8x8 ins. 10 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stone $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And marked stone 1/16 on N. face.	
20.00	Canon bears N.	-50
25.00	Top of ridge bears N.	430
28.00	Canon bears N.	-50