

Sub Subdivision of Township 3 North Range 35 East

| | | |
|---|---|---------------|
| Chains | <p>Sec. cor. Dug pits 18x18x12 ins, E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground, marked 1/16 S. on N. face.</p> | |
| 38.48 | <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> | |
| 57.72 | <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised a mound of earth 1½ ft. high 3½ base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> | |
| 76.96 | <p>To point of beginning. Land rolling. Soil 1st rate.</p> | |
| East on random through S. ½ of Sec. 22. | | |
| | | Va. 21° East. |
| | <p>Commencing at 1/16 Sec. cor. 20 chains N. of S. W. cor. of Sec. 22.</p> | |
| | <p>Set temporary cors. at 20, 40 and 60 chains. And at</p> | |
| 76.80 | <p>Intersect E. bdy. 42 lks. S. of 1/16 Sec. cor. Thence S. 89° 42' W. on true line.</p> | |
| 15.00 | <p>Gulch bears S. W.</p> | -100 |
| 19.20 | <p>Set basalt stone 10x10x10 ins. 6 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it.</p> | |
| 24.00 | <p>Gulch bears N. W.</p> | -50 |
| 38.40 | <p>Set basalt stone 12x8x6 ins. 8 ins. in the ground for ¼ Sec. cor. marked ¼ on N. face. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. And raised mound of earth</p> | |