

Sub Subdivision of Township 3 North Range 35 East.

Chains	$1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.	
57.60	Set basalt stone 12x8x7 ins. 8 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. And raised mound of stone $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. over it.	
76.80	To point of beginning. Land rolling. Soil 1st rate. Not cultivated.	
East on random through Center of Sec. 22.		
	Va. 21° East.	
	Commencing at $\frac{1}{4}$ Sec. cor. bet. Secs. 21 & 22.	
	Set temporary cors. at 20, 40 and 60 chains. And at	
77.28	Intersect E. bdy. 35 lks. S. of $\frac{1}{4}$ Sec. cor. Thence S. $89^{\circ} 45'$ W. on true line.	
1.00	Gulch /S. W.	-20
19.32	Set basalt stone 9x8x7 ins. 6 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. of stone $5\frac{1}{2}$ ft; dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.	
29.00	Gulch S. W.	-20
38.64	Set basalt stone 12x8x8 ins. 8 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits 18x18x12 ins. E. & W. of stone $5\frac{1}{2}$ ft. dist. And raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.	
57.97	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 on N. face.	
77.28	To point of beginning. Land rolling. Soil 1st. rate. Not cultivated, good grass.	