

Sub Subdivision of Township 3 North Range 35 East.

Chains	East on random through N. $\frac{1}{2}$ of Sec. 22.	Va. $21\frac{1}{2}^{\circ}$ East.
	Beginning at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet. Secs. 21 & 22.	
	Set temporary cors. at 20, 40 and 60 chains. And at	
77.32.	Intersect E. bdy. 30 lks. S. of 1/16 Sec. cor. Thence S. $89^{\circ} 47'$ W. on true line.	
1.00	Gulch bears S. W.	-20
19.33	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits, 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.	
38.66	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face	
57.99	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.	
77.32	To point of beginning.	
	Land level,	
	Soil 1st rate.	
	East on random through S. $\frac{1}{2}$ of Sec. 15	
		Va. $21\frac{1}{2}^{\circ}$ East.
	Commencing at 1/16 Sec. cor. 20 chains N. of S.W. cor. of Sec. 15.	
	Set temporary cors. at 20, 40 and 60 chains. And at	
77.40	Intersect E. bdy. 40 lks. S. of 1/16 Sec. cor. Thence S. $89^{\circ} 43'$ W. on true line	
19.35	Deposited charred stake 12 ins. in the ground for 1/16	