

Sub Subdivision of Township 3 North Range 35 East

Chains 57.91	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 1/2 ft. dist. raised mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. And in E. pit drove stake 2 ft, long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face</p>
77.22	<p>To point of beginning. Land rolling. Soil 1st rate. Not cultivated.</p>
<hr/> <p>East on random through N. 1/2 of Sec. 15. Va. 21 1/2° East. Commencing at 1/16 Sec. cor. 20 chains. N. of 1/4 Sec. cor. bet. Secs. 15 & 16.</p>	
77.36	<p>Set temporary cors. at 20, 40 and 60 chains. And at Intersect E. bdy. 42 lks. S. of 1/16 Sec. Sec. cor. Thence S. 89° 42' W. on true line.</p>
19.34	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 1/2 ft. dist. raised mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
38.63	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 1/2 ft. dist. raised mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
58.02	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 1/2 ft. dist. raised mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground, marked 1/16 S. on N. face.</p>
70.00	<p>Canon bears N.</p>