

Sub Subdivision of Township 3 North Range 35 East.

Chains		
77.36	To point of beginning. Land level. Soil 1st rate	
	East on random through S. $\frac{1}{2}$ of Sec. 10. Va. $21\frac{1}{2}^{\circ}$ East. Commencing at $\frac{1}{16}$ Sec. cor. 20 chains N. of S.W. cor. of Sec. 10. Set temporary cors. at 20, 40 and 60 chains. And at	
77.35	Intersect E. bdy. 50 lks. S; of $\frac{1}{16}$ Sec. cor. Thence S. $89^{\circ} 39'$ W. on true line.	
11.50	Canon N. W.	-70
19.34	Set basalt stone 12x10x4 ins. 8 ins. in the ground for $\frac{1}{16}$ Sec. cor. marked $\frac{1}{16}$ on N. face. Dug pits 18x18x12 ins. E. & W. of stone, $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.	
38.68	Set basalt stone 12x10x8 ins. 8 ins. in the ground for $\frac{1}{16}$ Sec. cor. marked $\frac{1}{16}$ on N. face. Dug pits, 18x18x12 ins. E. & W. of stone $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.	
58.02	Set post 3 ft. long 3 ins. square 24 ins. in the ground for $\frac{1}{16}$ Sec. cor. marked $\frac{1}{16}$ S. on N. face. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base around post.	
77.35	To point of beginning. Land rolling. Soil 1st rate. Not cultivated.	
	East on random through Center of Sec. 10. Va. 21° East. Commencing at $\frac{1}{4}$ Sec. Cor. bet. Seps. 9 & 10. Set temporary cors. at 20, 40 and 60 chains. And at	
77.30	Intersect E. bdy. 50 lks. S. of $\frac{1}{4}$ Sec. cor. Thence S. $89^{\circ} 39'$ W. on true line.	