

Sub. Subdivision of Township 3 North Range 35 East.

Chains 70.00	Canon and Wagon Road S.	-300
80.10	To point of beginning. Land Rolling. Soil 2nd rate, some rocky. Not cultivated.	
<p align="center">East on random through N. $\frac{1}{2}$ of Sec. 39. Va. 21° East. Commencing at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet. Secs. 32 & 33. Set temporary cors. at 20, 40 and 60 chains, And at</p>		
80.10	Intersect E. bdy. 36 lks. S. of 1/16 Sec. cor. Thence S. 89° 45' West on true line.	
20.02	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.	
24.00	Gulch bears S. W.	-200
39.50	Gulch bears S.	-250
39.90	Gulch and Wagon Road	
40.05	Set post 3 ft. long 3 ins. square 24 ins. in the ground for 1/16 Sec. cor/ marked 1/16 S. on N. face. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it.	
60.08	Set basalt stone 16x14x8 ins. 10 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. of stone 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it.	
80.10	To point of beginning. Land rolling. Soil 1st rate.	
<p align="center">East on random through S. $\frac{1}{2}$ Sec. 28. Va. 21° East.</p>		