

Sub Subdivision of Township 3 North Range 35 East.

Chains			
	Commencing at 1/16 Sec. cor. 20 chains N. of S. W. cor. of Sec. 28.		
	Set temporary cors. at 20, 40 and 60 chains. And at		
80.08	Intersect E. bdy. 42 lks. S. of 1/16 Sec. cor. Thence S. 89° 42' W. on true line		
20.02	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.		
30.00	Gulch N. W.	-50	
40.04	Set basalt stone 9x8x7 ins. 6 ins. in the ground for 1/16 Sec. cor, marked 1/16 S. on N. face, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it.		
45.00	Gulch and Wagon Road		-150
60.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.		
80.08	To point of beginning. Land rolling. Soil 1st rate.		
	East on random through Center of Sec. 28. Va. 20½° East.		
	Commencing at ¼ Sec. cor. bet. Secs. 28 & 29.		
	Set temporary cors. 20, 40 and 60 chains. And at		
80.00	Intersect E. bdy. 45 lks. S. of ¼ Sec. cor. Thence S. 89° 41' W. on true line.		
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it.		