

Sub Subdivision of Township 3 North Range 35 East.

Chains	
80.00	<p>Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>To point of beginning.</p> <p>Land gently rolling.</p> <p>Soil 1st rate.</p> <p>Not cultivated.</p>
80.08	<p>East on random through S. ½ of Sec 21.</p> <p style="text-align: right;">Va. 20° East.</p> <p>Commencing at 1/16 Sec. cor. 20 chains N. of S.W.cor. Sec. 21.</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at Intersect E. bdy. 46 lks. S. of 1/16 Sec. cor. Thence S. 89° 40' West on true line.</p>
20.02	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
40.04	<p>Set basalt stone 12x8x7 ins. 8 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it.</p>
50.00	<p>Gulch bears N.W. C-50</p>
60.06	<p>Set basalt stone 10x8x8 ins. 6 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. And raised a mound of earth 1½ ft. high 3½ ft. base over it. And marked stone 1/16 on N. face.</p>
70.00	<p>Gulch Course N. -20</p>
80.08	<p>To point of beginning.</p> <p>Land level.</p> <p>Soil 1st rate.</p> <p>Not cultivated.</p>