

Sub Subdivision of Township 3 North Range 35 East.

Chains 40.10	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist, raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
60.15	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. in the ground E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S on N. face.
80.20	To point of beginning. Land level, soil 1st rate. Not cultivated. Sept. 28, 1887.
East on random through S. ½ of Sec. 16. Va. 20° East. Commencing at 1/16 Sec. cor. 20 chains N. of S.W. cor. of Sec. 16. Set temporary cors. at 20, 40 and 60 chains. And at	
80.16	Intersect E. bdy. 27 lks. S. of 1/16 Sec. cor. Thence S 89° 48' West on true line.
20.04	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.
40.08	Set basalt stone 12x12x12 ins. 8 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. And raised mound of earth 1½ ft. high 3½ ft. base over it.
60.12	Set basalt stone 12x10x4 ins. 8 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised mound