

Sub Subdivision of Township 3 North Range 35 East.

Chains	Square 12 ins. in the ground marked 1/16 S. on N. face.
79.80	To point of beginning. Land rolling. Soil 1st rate. Not cultivated. Good pasture land.
	East on random through N. $\frac{1}{2}$ of Sec. 9. Var. 20° East. Commencing at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. between Sec. 8 & 9. Set temporary cors. at 20, 40 and 60 chains. And at 79.70 Intersect E. bdy. 50 lks, S. of 1/16 Sec. cor. Thence S. 89° 39' West on true line. 19.92 Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 ^S / _N on N. face. 25.00 Enter field N. & S. 31.00 Catch North. 39.85 Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face. 59.37 Leave field. 59.77 Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face. 79.70 To point of beginning. Land rolling. Soil 1st rate. Partly cultivated.