

Sub Subdivisions of Township 3 North Range 35 East.

Chains	<p>12 ins. in the ground marked 1/16 S. on N. face. As the next cor. on this line will be outside of the Diminished Reserve, I discontinue line at this point N. 89° 30' East on true line through N. 1/4 of Sec. 4. Va. 20° East. Commencing at 1/16 Sec. cor. 20 chains N. of 1/4 Sec. cor. bet. Secs 4 & 5.</p>
79.90-	<p>The length of this line will be at And at</p>
19.92	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pit 18x18x12 ins. E. & W. of stake 5 1/2 ft. dist. raised mound of earth 1 1/2 ft. high 3 1/2 ft, base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face. Discontinued line at this point Land mostly level. Soil 1st rate, All cultivated.</p>
	<p>Sept. 29, 1887.</p>
	<p>East on random through Center of Sec. 32. Va. 21° East.</p>
	<p>Beginning at 1/4 Sec. cor. bet Secs. 31 & 32.</p>
	<p>Set temporary cors. at 20, 40 and 60 chains. And at</p>
80.08	<p>Intersected E. bdy. 23 lks. S. of 1/4 Sec. cor. Thence S. 89° 50' W. on true line.</p>
7.00	<p>Gulch bears S.</p>
20.02	<p>Set basalt stone 10x8x6 ins. 6 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. in E. & W. of stone 5 1/2 ft. dist. and raised mound of earth 1 1/2 ft. high 3 1/2 ft. base over it.</p>
40.04	<p>Deposited charred stake 12 ins. in the ground for 1/4 Sec. cor. Dug pits 18x18x12 ins. in E. & W. of stake 5 1/2 ft. dist. raised mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. And in E. pit drove stake 2ft. long 2ins. sq. 12 ins. in the ground marked 1/4 S. on N. face.</p>

-150

+200