

Sub Subdivision of Township 3 North Range 35 East.

Chains 60.06.	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p>
73.00	Gatch bears S.
80.08	<p>To ¼ Sec, cor. and point of beginning. Land rolling. Soil 1st rate. Not cultivated.</p>
<p>East on random through N. ½ of Sec. 32. Va. 21° East. Commencing at 1/16 Sec. cor. 20 chains N. of ¼ Sec. cor. bet Secs. 31 &amp; 32.</p>	
80.00	<p>Set temporary cors. at 20, 40 and 60 chains. And at Intersect E. bdy. 17 lks. S. of 1/16 Sec. cor. Thence S. 89° 52' West on true line.</p>
20.00	<p>Deposited charred stake 3 ft. long 3 ins. square 24 ins. in the ground for 1/16 Sec. cor. marked 1/16 S. on N. face. Dug pits 18x18x12 ins. E. &amp; W. of post 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base around post.</p>
40.00	<p>Set post 3 ft. long 3 ins. square 24 ins. in the ground for 1/16 Sec. cor. marked 1/16 S. on N. face. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base around post.</p>
60.00	<p>Set basalt stone. 9x8x7 ins. 6 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face. Dug pits 18x18x12 ins. E. &amp; W. of stone 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base around it.</p>
80.00	<p>To 1/16 Sec. cor. and point of beginning. Land mostly level. Soil 1st rate. Not cultivated.</p>

-200