

Sub Subdivision of Township 3 North Range 35 East.

Chains.	<p>East on random through Center of Sec. 20 Va. 20° East.</p> <p>Began at $\frac{1}{4}$ Sec. cor. bet. Secs. 19 & 20.</p> <p>Set temp. cors. at 20, 40 and 60 chains. And at</p> <p>80.00 Intersect E. bdy. 15 lks. S. of $\frac{1}{4}$ Sec. cor. Thence S. 89° 54' W. on true line.</p> <p>20.00 Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>40.00 Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ft, dist. raised mound of earth 1$\frac{1}{2}$ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.</p> <p>55.00 Fence & enter field N. & S.</p> <p>60.00 Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$ ft. dist. raised mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>80.00 To $\frac{1}{4}$ Sec. cor. point of beginning. Land rolling. Soil 1st rate. Partly under cultivation.</p>
	<p>East on random through N. $\frac{1}{2}$ of Sec. 20. Va. 19$\frac{3}{4}$° East.</p> <p>Began at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor bet. Secs. 19 & 20.</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at</p> <p>80.00 Intersect E. bdy. 12 lks S. of 1/16 Sec. cor. Thence S. 89' 55' W. on true line</p> <p>20.00 Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5$\frac{1}{2}$</p>