

Sub Subdivision of Township 3 North Range 35 East

Chains.	
40.00	<p>ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $1/16$ S. on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for $1/16$ Sec. cor. Dug pits $18 \times 18 \times 12$ ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $1/16$ S. on N. face.</p>
55.00	<p>Fence and Enter field N. & S.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for $1/16$ Sec. cor. Dug pits $18 \times 18 \times 12$ E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. the ground marked $1/16$ S. on N. face.</p>
80.00	<p>To point of beginning.</p> <p>Land rolling, soil 1st rate.</p>
<p>East on Random through S. $\frac{1}{2}$ of Sec 17</p>	
<p>Va. 20° East.</p>	
<p>Began at $1/16$ Sec. cor. 20 chains N. of S. W. cor. of Sec. 17.</p>	
80.04	<p>Set temporary cors. 20, 40 and 60 chains. And at Intersect E. bdy. 10 lks. S. of $1/16$ Sec. cor. Thence S. $89^\circ 56'$ W. on true line.</p>
20.01	<p>Deposited charred stake 12 ins. in the ground for $1/16$ cor. Dug pits $18 \times 18 \times 12$ ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $1/16$ S. on N. face.</p>
40.02	<p>Deposited charred stake 12 ins. in the ground for $1/16$ Sec. cor. Dug pits $18 \times 18 \times 12$ ins. E. & W. of stake $5\frac{1}{2}$ dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $1/16$ S. on N. face</p>