

## Sub Subdivision of Township 3 North Range 35 East

Chains 60.03	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>Branch water hole N. To point of beginning.</p>
60.50 80.04	<p>Land rolling, soil 1st rate, partly cultivated.</p>
Sept. 30, 1887.	
<p>East on random through Center of Sec. 17.</p>	
<p>Va. 20° East.</p>	
<p>Began at ¼ Sec. cor. bet Sec. 17 &amp; 18.</p>	
<p>Set temporary cors. at 20, 40 and 60 chains. And at</p>	
80.00	<p>Intersect E. bdy. 7 lks. S. of ¼ Sec. cor. Thence S. 89° 57' West on true line.</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for ¼ Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked ¼ S. on N. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. &amp; W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
70.00	<p>Ditch bears N.</p>
80.00	<p>To point of beginning.</p> <p>Land slightly rolling.</p> <p>Soil 1st rate.</p> <p>Mostly cultivated.</p>