

100

Sub Subdivision of Township 3 North Range 35 East.

Chains	
	<p>East on random through N. $\frac{1}{2}$ of Sec. 17.</p> <p style="text-align: right;">Va. 20 E.</p> <p>Began at $\frac{1}{16}$ Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet Secs. 17 & 18.</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at</p>
80.12	<p>Intersect E. bdy. 12 lks. S. of $\frac{1}{16}$ Sec. cor. Thence S. $89^{\circ} 55'$ W. on true line.</p>
20.03	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.</p>
40.06	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.</p>
60.09	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked $\frac{1}{16}$ S. on N. face.</p>
80.12	<p>To point of beginning.</p> <p>Land rolling, Soil good, mostly cultivated.</p> <p>No water or timber.</p>
	<p>East on random through S. $\frac{1}{2}$ of Sec. 8.</p> <p style="text-align: right;">Va. 20° East.</p> <p>Began at $\frac{1}{16}$ Sec. cor. 20 chains N. of S.W. cor. of Sec. 8.</p> <p>Set temporary Cors. at 20, 40 and 60 chains. And at</p>
80.08	<p>Intersect E. bdy. 12 lks. S. of $\frac{1}{16}$ Sec. cor. Thence S. $89^{\circ} 55'$ W. on true line.</p>
20.02	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{16}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base</p>