

Sub Subdivision of Township 3 North Range 35 East.

Chains.	
	ft. dist. raised mound of earth $1\frac{1}{2}$ ft. $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
80.14	To point of beginning. Land rolling. Soil fine. All cultivated.
East on random through N. $\frac{1}{2}$ of Sec. 8.	
Va. 20° East.	
Began at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet. Secs. 7 & 8.	
Set temporary cors. at 20, 40 and 60 chains. And at	
80.20	Intersect E. bdy. 12 lks. S. of 1/16 Sec. cor. Thence S. 89° 55' W. on true line.
20.05	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
40.10	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
60.15	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
80.20	To point of beginning. Band level, soil 1st rate. All cultivated.