

Sub Subdivisions of Township 3 North Range 35 East.

Chains	mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base around post.
63.00	Leave field.
74.75	Wagon Road bears N.
80.00	To point of beginning.
	Land mostly level.
	Soil fine, all cultivated.
West on random through Center of Sec. 31. Va. 21° East.	
	Began at $\frac{1}{4}$ Sec. cor. bet. Secs 31 & 32.
	Set temporary cors. at 20, 40 and 60 chains. And at
77.70	Intersect W. bdy. 12 lks. N. of $\frac{1}{4}$ Sec. cor. Thence N. $89^{\circ} 55'$ East. on true line.
2.05	Wagon Road N. & S.
17.70	Deposited charred stake 12 ins. in the ground for $1/16$ Sec. cor. Dug pits $18 \times 18 \times 12$ ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $1/16$ S. on N. face.
37.70	Set basalt stone $12 \times 10 \times 8$ ins. 8 ins. in the ground for $\frac{1}{4}$ Sec. cor marked $\frac{1}{4}$ on N. face. Dug pits $18 \times 18 \times 12$ ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.
49.05	Gulch bears S.
57.70	Deposited charred stake 12 ins. in the ground for $1/16$ Sec. cor. Dug pits $18 \times 18 \times 12$ ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $1/16$ S. on N. face.
77.70	To point of beginning. Land rolling, soil 2nd rate. Not cultivated.
	Oct. 1st. 1887.