

176
Sub Subdivision of Township 3 North Range 35 East.

Chains.	
37.08	<p>over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
57.08	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
77.08	<p>To point of beginning.</p> <p>Land level.</p> <p>Soil 1st rate.</p> <p>Not cultivated.</p>
West on random through Center of Sec. 30.	
Va. 21° East.	
77.12	<p>Began at ¼ Sec. cor. of Secs. 29 & 30.</p> <p>Set temporary cors. at 20, 40 and 60 chains. And at Intersect W. Bdy. 25 lks. N. of ¼ Sec. Thence</p> <p>N. 89° 49' E. on true line.</p>
17.12	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p>
37.12	<p>Deposited charred stake 12 ins. in the ground for ¼ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked ¼ S. on N. face.</p>