

Sub Subdivision of Township 3 North Range 35 East.

Chains	
	West on random through Center of Sec. 18. Va. 20° East. Began at $\frac{1}{4}$ Sec. cor. bet. Sec. 17 & 18. Set temporary cors. at 20, 40 and 60 chains. And at
77.29	Intersect W. bdy. 14 lks. N. of $\frac{1}{4}$ Sec. cor. Thence N. 89° 54' E. on true line
17.29	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12ins. in the ground marked 1/16 S. on N. face.
37.29	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.
57.29	Deposited charred stake 12ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12ins. in the ground marked 1/16 S. on N. face.
77.29	To point of beginning.
	Land rolling. Soil 1st rate. All cultivated.
	Oct. 3rd, 1887.
	West on random through N. $\frac{1}{2}$ of Sec. 18. Va. 20° East. Began at 1/16 Sec. cor. 20 chains N. of $\frac{1}{4}$ Sec. cor. bet. 17 & 18. Set temporary cors. at 20, 40 and 60 chain. And at
77.35	Intersect W. bdy. 16 lks. N. of 1/16 Sec. cor. Thence N. 89° 53' E. on true line.
17.35	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5 $\frac{1}{2}$ ft. dist. raised mound of earth 1 $\frac{1}{2}$ ft. high 3 $\frac{1}{2}$ ft. base over it. And in E. pit drove stake 2ft. long 2ins. square 12 ins. in the ground marked 1/16 S. on N. face