

Sub Subdivision of Township 3 North Range 35 East.

Chains 37.35	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
57.35	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
77.35	To point of beginning. Land rolling.
Soil	Soil 1st rate. All cultivated.
West on random through S. ½ of Sec. 7 Va. 20° East.	
Began at 1/16 Sec. cor. 20 chains N. of S. E. cor. of Sec. 7.	
Set temporary cors. at 20, 40 and 60 chains, And at	
77.42	Intersect W. bdy. 16 lks. N. of ¼ Sec. cor. Thence N. 89° 53' E. on true line.
1.00	Wagon Road N. & S.
17.42	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
37.42	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. Dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on