

Exteriors of Township 3 North Range 34 East

Chains

Square broken off marked S. 19 on N.E. S 30 R., 35 E on S. E. S 25, R 34, S. on S.W. & S 24 T. 3 N. on N.W. faces with 4 notches on N. & 2 on S. edges. with a pit in each Sec.  $5\frac{1}{2}$  ft. dist. partly filled. Mound badly scattered. Reset post in earth mound, south between Sec. 25 & 30.

To cor. Secs. 25, 30, 31 & 36 a post 4 ft. long 4 ins. square firmly set in the ground marked S 30, T 3 N. N E. S 31 R 35, E on S. E. S 36 S. W. S 25, R 34, E on N. W. faces. I cut 5 notches on N & 1 on S. edges. Pits and mound defaced by plow.

Subdivision of Township 3 North Range 35 East.

Examination of Corners.

Going East between Secs. 30 & 31. I found that the  $\frac{1}{16}$  &  $\frac{1}{4}$  corners were all destroyed being plowed up. Cors. to Secs. 29, 20, 31 & 32. was plowed up found stake by fence marked S. 29, T 3, N on N.E. S 32, R 35, E. on S. E. S 31 on S. W. & S 30 on N. W. faces, with 5 notches on E & 1 on S. edges, could find no trace of pits or mound.

Corners to Secs. 20, 21, 28 & 29. A post 2 ft. by 4 inches square above ground. Marked S. 21 T. 2 N on NE., S 28 on S.E., S 29 on SW., S. 20 R. 35 E on N.W. faces, 4 notches on E. edge S. edge split off, cut 2 notches on S edge, earth mound & pits well preserved. East bet. Secs. 21 & 28.  $\frac{1}{16}$ ,  $\frac{1}{4}$  &  $\frac{1}{16}$  corners in tolerably good condition.

Found cor., Secs 21, 22, 27 & 28 a charred stake with pits in each Sec.  $5\frac{1}{2}$  ft. dist. stake in S. E. Pits marked S. 22 T 3 N. on NE. S 27 R. 35 E on S.E. S. 28 S.W. & S. 21 on N.W. faces, with 3 notches on N.E. & 2 on S. edges. Pits in good repair earth mound partly destroyed.