

Retracement S. Bdy. T. 3 N. R. 35 E.

Chains

Field Notes

Survey of the Retracement Resurvey and Subdivision of Section 34, Township No. 3 North Range No. 35 East. And the Survey of Tract No 37.8f the Willamette Meridian, In the State of Oregon.

Executed by. -Joseph A. Ganong, U.S. Cadastral Engineer In the capacity of U.S. Surveyor, under Special Instructions dated Nov. 4, 1922, issued by the United States General to govern surveys included in Group No. 100, which were approved by the Commissioner of the General Land Office, Nov. 29, 1922. And assignment Instructions dated Mar. 26, 1923.

Survey commenced October 27, 1923.

Survey completed October 30, 1923.

Note: All corners hereinafter described which are at variance with the original record of the Public Land Survey and not established by me, are restorations made by the Indian Service in making Allotment Surveys and are now the best obtainable evidence of the location of the record corners, and are here particularly described as follows: All posts are 2-inches galvanized iron pipe, 3½ ft. long and brass cap toggled to the post, uniformly marked Indian Allotment Penalty \$250 For Removal; with blank space for the addition of appropriate marks, as section, township and range numbers.

I commence at the cor. of secs. 34 and 35. Of the Tp. in latitude 45°46'N., longitude 118°24'W., magnetic decl. 19-30'E., which is a 2-inch iron post, firmly set, and extending 12 ins. above ground, with brass cap marked

T3N	R35E
S34	S35

1919	

Thence; S. 89°50'W., retracing the S. bdy. of Sec. 34.

Along gentle N. slope, through grain field.

- 1.70 Enter thicket, bears N. and S.
 - 1.80 Dry draw, course N. W.
 - 4.40 Leave theicket, bears N. and S., enter field and descend
 - 9.90 Descend over rim-rock, 20 ft. high, bears NE. and SW.
 - 12.50 Bottom of descent, bears N.E. and SW. thence over level land on river bottom through dense undergrowth.
 - 19.97 Intersect the E. 1/16 sec. cor. on the S. bdy. of sec. 34, which is a 2-inch iron post, firmly set, extending 12 inches above ground, with a mound of stone, 2 ft. base 1½ ft. high N. of cor., and brass caps marked.
- | | |
|--------|------|
| T3N | R35E |
| E 1/16 | S34 |
| ----- | |
| 1919 | |
- 22.15 Road, bears NE. and SW.
 - 22.65 Right-of-way fence, bears N. 57½°E. and S. 57½° W.
 - 23.90 Center of track, O.W.R.R. & N.R.R., bears N. 57½° 30'E. and S. 57½° 30' W.