

Retracement S. Bdy. T. 3 N., R. 35 E.

Chains							
25.25	Right-of-way fence, bears N. $57\frac{1}{2}^{\circ}$ E. and $57\frac{1}{2}^{\circ}$ W.						
27.05	Road, bears NE. and SW.						
34.42	Intersect the witness cor. to the $\frac{1}{4}$ Sec. cor. on the S. bdy. of Sec. 34, which is a 2-inch iron post, firmly set, extending 12 inches above the ground, with a mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, E. of cor., and brass cap marked.						
	<table border="1"> <tr> <td>T3N</td> <td>R35E</td> </tr> <tr> <td>WC $\frac{1}{4}$</td> <td>S34</td> </tr> <tr> <td colspan="2" style="text-align: center;">1919</td> </tr> </table>	T3N	R35E	WC $\frac{1}{4}$	S34	1919	
T3N	R35E						
WC $\frac{1}{4}$	S34						
1919							
34.95	Left bank of Umatilla River, course S. 70° W., thence across river.						
39.94	At North edge of river on flat gravel bar subject to overflow, is a point for $\frac{1}{4}$ sec. cor. as hereinafter determined. am unable to find any evidence of the old $\frac{1}{4}$ sec. cor., set temp. cor. Thence across river.						
44.70	Left bank of Umatilla River, course N. 20° W.						
54.20	Left bank of Umatilla River, 150 lks. wide, course SW.						
59.50	Dry Ravine, course S. ascend SE. slope, 196 ft.						
70.45	Top of spur, slope, S., descend W. slope 70 ft.						
74.30	Spring branch, 1 lk. wide, in ravine, course S., ascend E. slope, 114 ft. to						
79.88	Intersect the cor. of Sec. 33 & 34, which is a 2-inch iron post, firmly set in a mound of stone, with brass cap marked						
	<table border="1"> <tr> <td>T3N</td> <td>R35E</td> </tr> <tr> <td>S33</td> <td>S34</td> </tr> <tr> <td colspan="2" style="text-align: center;">1919</td> </tr> </table>	T3N	R35E	S33	S34	1919	
T3N	R35E						
S33	S34						
1919							
	Land, rolling and level, Soil, rich sandy loam, 1st rate and rocky 4th rate; Timber, scattering balm. Undergrowth, thorn, briars and vines						
Retracement-Resurvey Subdivision T.3 N., R. 35 E.							
From the cor. of secs. 34 and 35 on the S. bdy. of the Tp. N1 $^{\circ}$ 15'W., retracing the line bet. secs. 34 and 35; at 19.51 chs. fall 1 lk. W. of the S. $\frac{1}{16}$ sec. cor. at 39.80 chs. fall 2 lks. W. of the $\frac{1}{4}$ sec. cor.							