

Retracement S. Bdy. T. 3 N., R. 35 E.

Chains

And at 79.94 chs. fall 34 lks. W. of the cor. of secs. 26, 27, 24 and 35.

From the cor. of secs. 34 and 35 on the S. bdy. of the Tp.

N. 1°13'W., retracing the line bet. secs. 34 and 35

Descend gradual N. slope 140 ft. through grain field.

5.45 Leave field, bears NW. and SE. enter dense undergrowth, and descend abruptly.

8.15 Bottom of descent, bears NE. and SW., thence over level bottom land.

13.25 Road, bears NE. and SW.

13.51 Right-of-way fence, bears N. 57½° E. and S. 57½° W. and S.

14.91 Center of track, O.W.R. & R.R. brs. N. 57°30'E. & S. 57°30'W.

15.78 Right-of-way fence bears N. 57½° E. and S. 57½° W.

19.51 Intersect the S. 1/16 sec. cor. of secs. 34 and 35 which is a 2-inch iron post, firmly set, extending 12 inches above ground, with a mound of stone, 3 ft. base 1½ ft. high W. of cor., and brass cap marked.

T3N	R35E
S 1/16	
S34	S35
1919	

27.60 Left bank of Umatilla River, 120 lks. wide, course N.W.

37.30 Beaver dam pond, bears E. and W.

38.10 Leave pond, bears E. and W., ascend steep rocky S. slope, 45 ft. to

39.80 Intersect the ¼ sec. cor. of secs. 34 and 35, which is a 2-inch iron post, firmly set in a mound of stone, with brass cap marked

T3N	R35E
S ¼	
S34	S35
1919	

Thence

N. 0° 46' continuing my measurements.

Ascend steep rocky S. slope, 855 ft.

42.80 Spring branch, 2 lks. wide, course SE.

57.70 Rim-rock 20 ft. high bears E. and W., thence along fence.

70.10 Fence bears E. and W. enter grain field.

73.50 Top of ascent bears E. and W., thence level land.