

Subdivision of Sec. 34, T 3 N., R. 35 E.

Chains	
	From the point for the $\frac{1}{4}$ Sec. cor. on the S. bdy. of sec. 34; N.0°44'W., on a true line along the meridional center subdivisional line of sec. 34. Over level river bottom.
9.40	Stream, 2 lks. wide, course SE.
10.10	Ascend open S. and SW. slope, 630 ft.
19.75	Apportioned distance.
	Set an iron post, 3 ft. long 1 in. diam., 27 ins. in the ground, for S. $\frac{1}{16}$ sec. cor., with brass cap marked <div style="text-align: center;"> C S1/16 S34 C 1923 </div> and raise a mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, W. of cor.
40.10	Intersect the center $\frac{1}{4}$ sec. cor., which is a 2-inch iron post, firmly set in a mound of stone, with brass cap marked <div style="text-align: center;"> T3N R35E Center $\frac{1}{4}$ S34 1919 </div> Continue ascent 45 ft. to
45.65	Top of high hill, slopes W., descend N.W. slope 215 ft.
61.60	Stream, 2 lks. wide in deep canyon, course SW. ascend SE. slope 255 ft.
80.60	Intersect the $\frac{1}{4}$ sec. cor. bet. sec. 27 and 34. Land, level and mountainous. Soil, rocky, 4th rate. Timber, scattering balm on river bottom. Undergrowth, none.
12.45	From the $\frac{1}{4}$ sec. cor. bet. secs. 34 and 35. S.89°51'W., on a true line along the latitudinal center subdivisional line of sec. 34. Ascend rocky SE. slope, 325 ft. Top of rocky spur, slopes S., descend S.W. slope, 185 ft.