

Subdivision of Sec. 34, T. 3 N., R. 35 E.

Chains 17.60	Dry ravine, course S., ascend SE. slope, 165 ft.
19.80	Set an iron post, 3 ft. long 1 in. diam., 27 ins. in the ground, for 1/16 sec. cor., with brass cap marked
	$\begin{array}{c} \text{E } 1/16 \\ \text{C} \frac{\quad}{\quad} \text{C} \\ \text{S } 34 \\ 1923 \end{array}$
	and raise a mound of stone, 2 ft. base, 1½ ft. high, N. of cor.
24.55	Top of ascent on S. slope of hill, thence ascend gradually along S. slope, 100 ft. to
39.60	Intersect the center ¼ sec. cor. of sec. 34. Descend steep W. slope, 370 ft. to
53.80	Stream, 3 lks. wide, course SW., ascend E. slope, 470 ft.
70.00	Top of ascent and fence, bears N. and S., enter grain field.
78.91	Intersect the ¼ sec. cor. bet, secs. 33 and 34. Land, mountainous and rolling. Soil, rocky 4th rate, 10 chs. sandy loam, 1st rate. Timber, none. Undergrowth, none.
19.00	From the S. 1/16 sec. cor. bet. secs. 34 and 35. S. 89°58' W., (calculated bearing) along the south subdivisional line of sec. 34. Over level bottom land through dense undergrowth. Left bank of Umatilla River, course SW. Point for SE. 1/16 sec. cor. falls in river therefore, Set iron post, 3 ft. long 1 in. diam., 27 ins. in the ground, for witness cor. to the SE. 1/16 sec. cor. with brass cap marked
	$\begin{array}{c} \text{WC SE } 1/16 \text{ S}34 \\ 1923 \end{array}$
	and raise a mound of stone, 2 ft. base, 1½ ft. high, W. of cor.
	Thence across river.