

Subdivision of Sec. 34, T 3 N., 35 E.

Chains
19.90 Point for SE 1/16 sec. cor. of sec. 34 in river, from which the E 1/16 sec. cor. on the S. bdy. of sec. 34, bears S.0°54'E., 19.63 chs. dist., and the center E 1/16 sec. cor., bears N. 0°54'W., 20.32 chs. dist.

21.40 Right bank of Umatilla River, ascend SE slope, 180 ft.

39.78 Intersect the S 1/16 sec. cor. of sec. 34, on the center meridional subdivisioal line.

Land, level and mountainous.

Soil, rocky, 4th rate.

Timber, balm and pine.

Undergrowth, thorn, briars, and vines.

Survey of Tract No. 37, T. 3 N., R. 35

I commence at the S1/16 sec. cor. bet. secs. 34 and 35 which I additionally mark for Cor. No. 4, Tract 37; the brass cap is now marked

T3N	R35E
S	1/16
TR37	
4	
S34	S35
1919	

an run

N.1°13'W., along E. bdy. of Tract No. 37, bet. secs. 34 and 35.

17.60 Point for Cor. No. 1, Tract 37 falling in beaver dam pond. Set an iron post, 3 ft. long 1 in. diam., 27 ins. in the ground, for witness cor. to Cor. No. 1, Tract 37, with brass cap marked

WC	
T3N	R35E
S34	
1	S35
TR37	
1923	

and raise a mound of stone, 3 ft. base, 2 ft. high, SW. of cor.

18.18 Point for Cor.No. 1, Tract 37, in beaver dam pond, impracticable to establish cor.