

Survey of Tract No. 37 T. 3 N., R 35 E.

Chains	
	Thence
	S. 74°30'W., along the N. bdy. of Tract no. 37.
	Over pond.
0.30	Leave pond, bears NE. and SW., thence over rocky land at foot of hill, sloping SE.
2.45	Set an iron post, 3 ft. long, 1 in. diam., 27 ins. in the ground, for Cor. No. 2 Tract 37, with brass cap marked
	and raise a mound of stone, 4 ft. base 3 ft, high, SE. of cor.
	Thence
	S. 13°40'W., along the W. bdy of Tract No. 37.
	Over rocky ground.
0.80	Right bank of Umatilla River, 100 lks. wide, course SW.
5.00	Enter scattering timber and dense undergrowth, bears E. and W.
18.04	Intersect the south latitudinal subdivisional line of sec. 34.
	Set an iron post, 3 ft. long 1 in. diam., 27 ins. in the ground, for Cor. No. 3, Tract 37, with brass cap marked
	from which
	A pine, 18 ins. diam., bears N.23½°E., 120 lks. dist., marked A P 3 T R 37 B T.
	A pine. 14 ins. diam., bears N.69½°E., 108 lks. dist., marked A P 3 T R 37 B T.
	Thence
	N.89°58'E., along the S. bdy. of Tract No. 37, and along the south latitudinal subdivisional line of Sec. 34.
	Over level land, through scattering timber and dense undergrowth.
7.01	To Cor. No. 4, Tract No. 37, identical with the S 1/16