

Township 3 North, Range 36 East

|        |   |      |
|--------|---|------|
| Chains | North on East boundary of Section 1.  | +50  |
|        | Var. 16° East.  |      |
| 40.00  | Set post corner for $\frac{1}{4}$ section, from which<br>A larch, 10 in dia. bears N.15°W. 32 lks.<br>A larch, 12 in dia. bears S.35°E. 26 lks.   | x    |
|        | Var. 20° East.  |      |
| 80.00  | Set post corner for Townships 3 & 4 North, Ranges 36 & 37 East, sections 1, 6, 31 & 36, from which<br>A fir, 10 in dia. bears N.10°W., 24 lks.<br>A fir, 8 in dia. bears N.55°E., 20 lks.<br>A fir, 6 in dia. bears S.45°E., 30 lks.<br>A fir, 12 in dia. bears S.3°W., 18 lks.<br>This line passes through thick timber, considerable of it fallen, timber, fir and larch. Undergrowth, the same, with willow. |      |
|        | September 5th, 1866.  |      |
|        | West on North boundary.   |      |
|        | Var. 19°30' East.   |      |
|        | At 40.00 and 80.00 chains, set half mile and mile post temporarily and intersect Western boundary 2 chains and 87 links South of post corner, 5 miles and 77 chains, 31 links.  | x    |
|        | Therefore the correction will be S.89°39' East on true line.  |      |
|        | September 25th 1866.  |      |
|        | S.89°39'E. on North boundary of Section 6.  |      |
| 37.31  | Set post corner for $\frac{1}{4}$ section. Deposited marked stone and made stone mound as per instructions.   | -60  |
| 53.00  | Pine creek, channel, dry, course S.75°W.  |      |
| 77.31  | Set post corner for sections 5, 6, 31 & 32 on steep hill side, facing the North, from which<br>A pine, 12 in dia. bears N.89°E. 94 lks.<br>A pine, 10 in dia. bears S.85°E. 90 lks.<br>A pine, 12 in dia. bears S.35°W. 12 lks.<br>A pine, 12 in dia. bears N.78°W. 65 lks.   | +300 |