

Subdivisional Lines of Township 3 North, Range 36 E. W.M.

Chains		
		Va. 15° East
79.20	To a point 33 lks. West of corner to Sections 13 and 24 Thence South along the East Boundary of Sec. 24.	
		Va. 20° East.
76.48	To a point 75 lks. West of corner to Sec. 24 and 25 showing an error of 352 lks. in the length of this line. September 27, 1878. South on the East Boundary of Sec. 25.	
		Va. 20° East.
79.65	To a point 45 lks. West of corner to Sec. 25 and 36 Thence South along the East Boundary of section 36.	
		Va. 20° East.
79.80	To a point 65 lks. West of corner to Townships 2 and 3 North, Ranges 36 and 37 East, showing a difference in measurement of 5.27 lks. in the 5 miles and but a small difference in coursing. Thence.	
	West on a blank line along the South Boundary of section 36.	
		Va. 21° East.
79.48	To a point 14 lks. North of stone corner to sections 35 and 36 on the South Boundary of the Township. Stone was very poorly marked. It should have had a stone mound built around it. Stone mounds make the most permanent monuments in this part of the country.	
	Having sufficiently tested the Exteriors and found the starting point for subdividing, and with Burt's Improved Solar Compass I run North between Sections 35 and 36.	
		Va. 18 $\frac{3}{4}$ ° East.
33.00	Top of ridge, extending NW. & SE. and enter timber	+500
40.00	Set fir post on NE. side of ridge for $\frac{1}{4}$ sec. cor. from which a	-150