

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains		
59.00	On spur extending West	+400
70.00	Ravine opens West.	-200
80.00	Set stone 15x10x6 on South face of hill for cor. to Sec. 26, 27, 34 and 35. Drove stake and raised mounds of stone around stake and stone in lieu of pits. Land: Surface, mountainous. Soil, 3rd rate. Some timber South of brook. North of brook, open hillside. Good bunch grass	+300
	East on a random line between Sec. 26 and 35. Va. 20° East.	
40.00	Set post for temporary $\frac{1}{4}$ sec. cor.	
79.68	Intersected N. and S. line 24 lks. North of corner to sections 25, 26, 35 and 28, from which cor. I run N. 89°50' West on a true line between sections 26 and 35. Va. 16°30' East.	
3.00	On ridge, course N. and S.	+50
34.00	Brook, 3 lks. wide, course North	-500
39.84	Set stone 15x8x6 on East side of ridge for $\frac{1}{4}$ sec. cor.	+150
66.00	On ridge, course NW. & SE.	+300
79.68	The cor. to Sec. 26, 27, 34 and 35. Land: Surface, mountainous. Soil, 3rd rate. Some timber. Fir and tamarack. Good bunch grass. Oct. 4th 1878	-200
	North between Sec. 26 and 27. Va. 20° East.	
11.00	On ridge extending NW.W.	+200
21.00	Ravine extending NW.	-200
40.00	Set stone 18x18x5 on SW. face near top of ridge for $\frac{1}{4}$ sec. cor.	-80
43.00	On ridge, NW. & SE.	+20
62.50	Spring-branch, course N.15°W.	-500
80.00	Set pine post on West hillside for cor. to Sec. 22, 23, 26 and 27. A fir, 8 in diam. brs. N. 60° E. 23 lks. dist. A fir 10 in diam. brs. S. 60° E. 17 lks. dist.	-100