

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains		
72.80	<p>A fir, 20 in diam. brs S. 73° E. 10 lks. dist.</p> <p>The cor. to Sec. 21, 22, 27 and 28.</p> <p>Land: Surface very broken. Soil, 2nd & 3rd rate: excellent timber on W. ½ mile; Scattering on E. ½ mile. Pine, tamrack & fir; good grass. About ¼ of Sec. 27 has excellent timber. Remainder of the section has scattering groves of timber.</p>	-200
North between sections 21 and 22.		
Va. 20°30' East.		
16.00	A house, bears N. 41° W. near river.	
33.25	Umatilla River 90 lks. wide, course at this point, West	-150
34.25	Road to LaGrand, E. & W. steep bluff.	
40.00	Set stone, 18x10x5 on steep South hillside for ¼ sec. cor.	+100
68.00	Spring branch, course SW.	
80.00	<p>Set stone 14x10x8 on East side of ridge for cor. to Sec. 15, 16, 21 and 22. Drove stake and built mounds of stone around stone and stake in lieu of pits.</p> <p>Land, surface, very broken and mountainous; river bottom narrow. Soil, 3rd rate. Small part on river bottom, first rate. Scattering timber South of river. Pine & fir; good grass</p>	+300
Oct 12, 1878.		
East on a random line between Sec. 15 and 22		
Va. 18° East.		
40.00	Set post for temporary ¼ sec. cor.	
72.86	<p>Intersected N. and S. line 14 lks. N. of cor. to Sec. 14, 15, 22 and 23, from which corner I run</p> <p>N. 89°54' West on a true line between Sec. 15 and 22.</p>	X
Va. 20°30' East.		
36.43	Set stone 18x10x5 on SE. side near top of bluff for ¼ sec. cor.	+600
60.50	Spring-branch, course SW.	-400
72.86	<p>The cor. to Sec. 15, 16, 21 and 22.</p> <p>Land: Surface, mountainous; Soil, 3rd rate; good grass.</p>	-100