

Subdivisional Lines of Township 3 North, Range 36 E. W. M.

Chains

Sept. 13th 1887.

Commencing at cor. to Secs. 32 and 33 on S. bdy. Township, which is post, 4 ft. long, 4 ins. square, 24 ins. in the ground, marked T 3 N S 33 on NE., R 36 E S 32 on NW. faces, in mound of stone I run North bet. Secs. 32 and 33.

Va. 21° East.

12.50 Top of ridge, W. †890

19.84 Set post, four ft. long, 4 ins. square, 24 ins. in the ground for C C to Secs. 32 and 33, marked U R C C on N., S 32 on W. and T 3 N R 36 E S 33 on E. faces, and dug pits 18x18x12 ins. at N. E. and W. of cor., 5½ ft. dist., and raised mound of stone and earth 2 ft. high, 4½ ft. base over it, from which the 37th mile cor. on U R bdy. bears S. 20° W. 120 lks. dist. Descend.

40.00 Set post 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ sec. cor., marked ¼ S on W. face, from which A pine, 6 ins. diam. bears N. 30° E. 8 lks. dist., marked ¼ S B T.
A pine, 6 ins. diam. bears N. 15° W. 10 lks. dist., marked ¼ S B T.

42.00 Gulch, W. -350

55.00 Sum. ridge, W. †400

62.00 Canon, W. -350

74.00 Top of ridge, W. †300

80.00 Set basalt stone 10x18x7 ins., 6 ins. in the ground for cor. to Secs. 28, 29, 32 and 33, marked with 1 notch on S. and 4 notches on East edges, and raised mound of stone, 2 ft. high, 4½ ft. base over it.

Land, very rough and mountainous.

80.00 chs.

Soil, 4th rate and rocky. Scattering pine and fir timber and underbrush of same.

East on ran. bet. Secs. 28 and 33.

Va. 20° East.