

Allotment

Subdivision of Township 3 North Range 36 East.

<p>Chains 31.25 39.62</p>	<p>Gulch course S.</p> <p>To corner to Secs. 13, 18, 19 and 24.</p> <p>Land mostly level along flat gulch.</p> <p>Soil, 1st rate.</p> <p>Good grass.</p>
	<p>From the <math>\frac{1}{4}</math> Sec. corner between Secs. 13 &amp; 18, on W. bdy. of Tp. which is a basalt stone 9x8x7 ins. 6 ins. in the ground marked <math>\frac{1}{4}</math> on W. face, from which</p> <p style="padding-left: 40px;">A pine, 24 ins. diam. bears N. 50° E. 22 lks. dist. marked <math>\frac{1}{4}</math> S B T.</p> <p style="padding-left: 40px;">A pine, 16 ins. diam., bears S. 83° W. 30 lks. marked <math>\frac{1}{4}</math> S B T.</p> <p>I run</p> <p>South on true line between Secs. 13 and 18.</p> <p style="text-align: right;">Var. 21° E.</p>
<p>9.50 10.00 20.00</p>	<p>Road course E. &amp; W.</p> <p>Set basalt stone 9x8x7 ins. 6 ins. in the ground for 1/32 corner, marked 1/32 on W. face, dug pits 18x18x12 ins. N. &amp; S. of stone 5<math>\frac{1}{2}</math> ft. dist. and raised mound of earth 1<math>\frac{1}{2}</math> ft. high 3<math>\frac{1}{2}</math> ft. base alongside.</p> <p>Set basalt stone 9x8x7 ins. 6 ins. in the ground for 1/16 &amp; 1/32 Sec. cor. marked 1/32 on N.E. &amp; 1/16 on S.E. face; dug pits 18x18x12 ins. N. and S. of stone 5<math>\frac{1}{2}</math> ft. dist. raised mound of earth 1<math>\frac{1}{2}</math> ft. high 3<math>\frac{1}{2}</math> ft. base over it.</p> <p>Land, on summit of Mt.</p> <p>Soil, 1st rate, good grass.</p>
	<p>From the 1/32 Sec. corner 10 chs. S. of <math>\frac{1}{4}</math> Sec. corner between Secs. 13 &amp; 18.</p> <p>I run</p> <p>S 89°28' E. on true line in Sec 18.</p> <p style="text-align: right;">Var. 21°E.</p>
<p>15.00</p>	<p>Enter brush and descend.</p>