

Subdivision of Township 3 North Range 36 East.

Chains	From the 1/16 Sec. corner, 20 chs. N. of the corner to Secs. 19, 24, 25 & 30, on W. bdy. of Tp.
	I run
Eac	East on true line in Sec. 19.
	Var. 19° E.
10.00	Gulch course N. W.
19.30	Set stone 10x8x7 ins. 6 ins. in the ground for 1/16 Sec. corner, marked 1/16 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.
38.30	Gulch course South.
39.30	Set basalt stone 11x8x6 ins. 7 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face, dug pits 18x18x12 ins. E & W of stone 5½ ft. dist. raised a mound of earth 1½ ft. high 3½ ft. base over it.
55.30	Begin to descend hill
59.30	Set basalt stone 12x9x8 ins. 8 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face, dug pits 18x18x12 ins. E & W. of stone 5½ ft. dist. raised a mound of earth 1½ ft. high 3½ ft. base over it.
	This corner stands on steep South slope.
	Land rolling.
	Soil, 1st rate.
	Grass and sunflower.
	June 7th, 1889.
	From the ¼ Sec. corner bet. Secs. 19 & 24, on West bdy. of Tp.
	I run
Ea	East on random line through Sec. 19.
	Var. 19° E.
79.30	Setting temporary corner at 20, 40 and 60 chains. And at Intersect the N. & S line 40 lks. S. of ¼ Sec. corner bet. Secs. 19 & 20, which is a basalt stone 18x10x8 ins. 12 ins. in the ground marked ¼ on W. face & mound of stone over it.