

Allotment

Section 19

Subdivision of Township 3 North Rangr 36 East.

Chains	
39.30	<p>dist. raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.</p> <p>Set post 3 ft. long 3 ins. square with charred stake 12 ins. in the ground for $1/16$ & $1/32$ Sec. corner, marked $1/16$ S. on S. & $1/32$ S. on N. face., from which</p> <p>A pine, 30 ins. diam. brs N. 30° E. 86 lks. dist. marked $1/16$ & $1/32$ S B T.</p> <p>A pine, 30 ins. diam. brs. N. 3° E. 124 lks. dist. marked $1/16$ & $1/32$ B T.</p> <p>Hand level last 15 chains in timber.</p> <p>Soil very rich.</p> <p>Grass and sunflower.</p>
	<p>From the $1/32$ Sec. corner, 10 chs. S. of corner to Secs. 18, 19, 13 & 24, on W. bdy. of Tp.</p>
	<p>I run</p> <p>S. $89^\circ 28'$ E. on a true line in Sec. 19.</p>
19.30	<p>Set basalt stone 12x10x9 ins. 9 ins. in the ground for $1/32$ Sec. corner marked $1/32$ on N. face and raised mound of stone over it on edge of flat Gulch.</p> <p>Pits impracticable.</p>
19.50	<p>Gulch course N. W.</p>
39.30	<p>Set basalt stone 12x9x8 ins. 9 ins. in the ground for $1/32$ Sec. corner marked $1/32$ on N. face, dug pits 18x18x12 ins. E.&W. of stone $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.</p> <p>Land level. Timber on whole line.</p> <p>Soil 1st rate.</p> <p>Pine and Bunch grass.</p>
	<p>June 8th, 1889.</p>
	<p>General Description :</p>
	<p>These lands are in Secs. 18 & 19 on the high summit North of Umatilla River. They are rolling & often run over brink and canyons. Good bunch grass & considerable pine timber.</p>