

1.  
South Boundary of Township 4 North of Range 37 East  
of the Willamette Meridian.

Surveyed by William H. Odell under Contract 114.

Dated July 2, 1866.

Chains Commencing at the South East Corner of Township No. 4  
North of Range 36 East of Willamette Meridian  
Thence  
East on South Boundary of Section 31.  
40.00 Set post Corner for  $\frac{1}{4}$  Section; from which  
A Larch, 12 ins. in diam., bears N. 33° E. 12 Lks.  
" " , 8 " " " , " S. 9° W. 32 "  
80.00 Set a post Corner Sections 31, 32, 5 & 6; from which  
A Fir, 8 ins. in diam., bears S. 6° E. 18 Lks.  
" " , 6 " " " , " N. 45° E. 11 "  
" " , 20 " " " , " S. 40° W. 40 "  
" " , 7 " " " , " N. 54° W. 32 "  
This line passes through thick timber, Fir, Larch & Pine.  
Undergrowth the same.

East between Sections 32 & 5.

Var. 21° East.

40.00 Set post corner for  $\frac{1}{4}$  Section; from which  
A Pine, 8 ins. in diam., bears N. 12° W. 22 Lks.  
A Fir, 6 " " " , " S. 15° W. 27 "  
80.00 Set post corner for Sections 4, 5, 32 & 33; from which  
A Fir, 20 ins. in diam., bears S. 59° W. 19 Lks.  
" " , 15 " " " , " S. 40° E. 59 "  
" " , 20 " " " , " N. 60° E. 40 "  
" " , 18 " " " , " N. 3° W. 9 "  
Land gently rolling, covered with thick timber, generally  
ly of small growth, Fir, Larch and Pine. Undergrowth  
the same.

The Southern Boundary of this Township should be surveyed  
and the South West half of the Township should be subdivided  
because of the valuable timber. The North East half is cut  
up by a deep canyon, very steep and difficult to cross.  
The lateness of the season prevented me from further  
prosecuting the survey.

October 11, 1866.