

Field Notes of Subdivision lines bounding Section 18 in Township No. 3 North of the Base Line of Range No. 37 East of Willamette Meridian; the Base Line of Range No. 37 East Surveyed by William H. Odell under Contract No. 114.

Dated July 2, 1866.

Chains	Commencing at a post on West Boundary of the Township Corner for Sections 18, 19, 13 & 24.	
	Thence	
	East between Sections 18 & 19.	
40.00	Set a basalt Stone 4 x 8 x 14 corner for $\frac{1}{4}$ Section.	
80.00	Set a post corner for Sections 17, 18, 19 & 20; from which	
	A Fir, 14 ins. in diam., bears E. 70 Lks., no other tree near, drove charred stake, dug pits and raised mound, as per instructions.	
	This line passes up divide between the Umatilla River and a deep canyon on the South, ride without timber good grass, soil stony.	
	North between Sections 17 & 18.	
	Var. 19° 30' East.	
5.00	Begin to descend hill.	
40.00	Made corner for $\frac{1}{4}$ Section on	50
	A Fir, 8 ins. in diam.; from which	
	A Fir, 8 " " " , bears S. 70° W. 22 Lks.	
	" " 10 " " " " S. 75° E. 25 "	
60.00	Umatilla River, 75 Lks.; wide on course West	600
65.60	Thomas & Buckle Toll Road, course East & West	
70.00	Begin to ascend hill.	
80.00	Set a post corner for Sections 7, 8, 17 & 18. Drove	100
	charred stake and made Stone Mound as per instructions.	
	This line passes down a steep hillside, timbered and rocky. The bottoms along the river are narrow and gravelly.	
	West on random between Sections 7 & 18.	
	Var. 20° East.	
40.00	Set temporary Corner for $\frac{1}{4}$ Section.	
80.23	Intersected West Boundary 33 Lks. South of Corner for Sections 7, 18, 12 & 13.	
	S. 89° 46' E. on true line.	
40.23	Set Basalt Stone 8 x 10 x 18 Corner for $\frac{1}{4}$ Section	175