

Township 3 N., R. 37 E., W.M.

Chains 80.23	To post Corner. over This line passes a succession of Ridges & Ravines, putting down toward the River. Timber in the Ravines; the Ridges bald with some grass. Soil stony.	
	Exterior Lines of T.No.3 N., R. 37 E., W.M. Surveyed by George S. Pershin under Contract No.304 Dated Sept. 19, 1878	
	From From the Cor. to T. 2 & 3 N., Ranges 37 & 38 E., I run N. on the Range Line between Sec. 36 & 31. Var. 21° 30' E.	
12.00	Enter timber, E. & W.	
38.25	Spring branch, course N.W.	
40.00	A Spruce, 4 ins. in diam. on N. slope for $\frac{1}{4}$ Sec. Cor. A Fir, 12 ins. in diam., bears E. 69 Lks. distant. " " 8 " " " " N. 46° W., 59 Lks.	-80
60.00	Begin steep descent.	-20
78.50	Brook, 6 lks. wide, course N.W.	-200
80.00	Set Stone, 16 x 12 x 4 on W. hillside for Cor. to Secs. 25, 36, 30 & 31 ; from which A Fir, 10 ins. in diam., bears N. 20° E. 26 Lks. dist. " " 8 " " " " S. 18° E. 17 " " " " 12 " " " " S. 82° W. 10 " " " " 10 " " " " N. 42° W. 23 " " Land surface on S. $\frac{1}{2}$ mile gently sloping. N. $\frac{1}{2}$ mile very broken; soil, third rate; heavy timber on S. 60 Chs.; on N. 20 Chs., scattering Tamarack, Fir, Pine & Spruce. April 16, 1879.	+20
	North on the E. Bdy. of Sec. 25 Var. 22° 00' E.	
40.00	Up irregular W. face of Mountain. Set Basalt Stone, 12 x 10 x 8 on W. mountain side for $\frac{1}{4}$ Sec. Cor. A Fir, 18 ins. in diam., bears N. 80° W., 25 Lks. dist	