

Township No.3 North, Range No.37 E.; Willamette Meridian

| | | |
|--------|---|-------|
| Chains | <p>A Fir, 30 Ins. in diam., bears S. 64° W. 170 Lks.dist. No other trees near.</p> <p>Land; surface, mountainous; Soil, 3rd rate & worthless. Good timber on North hillsides. Fir, Tamarack and Pine. Good grass on South hillsides.</p> <p style="text-align: right;">April 19, 1879</p> | |
| | <p>North on the East Boundary of Section 12</p> <p style="text-align: right;">Var. 18° 30' East</p> | |
| 12.00 | Enter timber, East & West | |
| 20.00 | Leave " " " " | |
| 30.00 | Enter " " " " | |
| 36.00 | Brook, 8 Lks. wide, course West | |
| 40.00 | A Fir, 7 ins. in diam. on S.W.hillside for $\frac{1}{4}$ Sec. Corner | |
| | A Fir, 12 ins. in diam., bears S.70° E. 25 Lks.distant | |
| | " " 6 " " " " S.72° W. 8 " " | |
| 44.50 | Brook, 25 Lks. wide, course S.W. | |
| 72.00 | Open glade | |
| 80.00 | Set Basalt Stone 14 x 12 x 4 on S.E. face of mountain in mound of stone for Corner to Sec. 1, 12, 6 & 7. | + 400 |
| | A Pine, 10 ins. in diam., bears N.18° E. 51 Lks. dist. | |
| | " " 18 " " " " S.70° E. 107 " " | |
| | " Fir 14 " " " " S.74° W. 160 " " | |
| | No other trees | |
| | Land; surface, mountainous. Soil, 3rd rate & worthless. Some good timber in places, but mostly scattering Tamarack Fir and Pine. | |
| | April 22, 1879. | |
| | <p>North on the East Boundary of Section 1</p> <p style="text-align: right;">Var. 19° 15' East.</p> | |
| 8.00 | Enter timber, course E. & W. | + 250 |
| 40.00 | Set Fir post on level for $\frac{1}{4}$ Sec. Corner. | |
| | A Spruce, 10 ins. in diam., bears N.84°E. 49 Lks.dist. | |
| | A Fir 28 " " " " S.60°W. 13 " " | |