

Township No.3 North, Range No.37 E., Willamette Meridian.

Chains	N.89° 48' E. on a true line along the N. Boundary of Sec. 3. Var.20° 15' E.	
40.00	Set a fir post in small open glade on level for $\frac{1}{4}$ Sec. Cor. A Pine, 11 ins. in diam., bears N. 5°E. 104 Lks. dist. A Fir 8 " " " " S.14°E. 135 " "	
68.00	Ravine and Spring branch S.	250
80.00	Set pine post on W. slope for corner to Secs.2,3,34 & 35 from which; A Fir, 24 ins. in diam., bears N.12° E.38 Lks. dist. " " 10 " " " " S.52° E.28 " " " " 22 " " " " S.40° W.30 " " " " " " " " N.40° W.53 " "	+100
	Land: surface mostly near level. Soil, 2nd & 3rd rate. Heavy timber, Fir, Pine, Tamarack & Spruce.	
	N.89°48' E. on a true line along the N. Boundary of Sec.2 Var.20° 15' E.	
40.00	Set a fir post on nearly level for $\frac{1}{4}$ Sec. Corner. A Fir, 12 ins. in diam., bears N.38°W. 30 Lks. dist. " " 14 " " " " S.30°W. 54 " "	
60.00	Enter burnt timber.	
80.00	Set spruce post on nearly level for corner to Secs. 1, 2, 35 & 36, from which; A Fir, 10 ins. in diam., bears S.48°E.229 Lks.dist. " " 48 " " " " N.43°W. 188 " "	+150
	No other green trees near. nearly Land; surface mostly level. Soil; 2nd & 3rd rate. Mostly heavy timber, Fir, Tamarack, Pine & Spruce.	
	N.89°48' E. on a true line along the N. Boundary of Sec.1. Var.20°30' E.	
15.00	Leave burn.	
30.00	Brook, 6 lks. wide, course S.W.	
39.00	" " " " " N.W.	
40.00	Set fir post on level for $\frac{1}{4}$ Sec. Cor., from which; A fir, 24 Ins. in diam., bears N.54°E. 115 Lks.dist.	