

Chains		
	<p>No trees near.</p> <p>Land; Surface mountainous. Soil; 3rd rate. A few strips of Fir and Tamarack timber in small gulches. Good grass on open ground.</p>	
	<p>East on a random line between Sec. 10 & 15.</p> <p style="text-align: right;">Var. 23° 30' E.</p>	
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.	
79.94	<p>Intersected N. & S. line 78 lks. S. of Cor. to Secs. 10, 11, 14 & 15, from which Cor.</p> <p>I run</p> <p>S. 89° 27' W. on a true line between Sec. 10 & 15.</p> <p style="text-align: right;">Var. 21° 30' E.</p>	
12.00	On ridge extending N. & S.	+80
39.97	<p>Set basalt Stone 14 x 10 x 4 on S. face of Spur for $\frac{1}{4}$ Sec. Cor.</p> <p>A Fir, 6 ins. in diam., bears N. 71° W. 45 lks. dist.</p> <p>" " 15 " " " " S. 26° W. 74 " "</p>	
46.00	Bottom of Gulch opens S.	-800
67.00	On Spur, extends S.	+300
79.94	<p>The Cor. to Sec. 9, 10, 15 & 16</p> <p>Land; surface mountainous. Soil; 3rd rate. Good timber in ravines and gulches, Fir, Tamarack & Pine. Good grass on open land.</p>	-200
	<p>North between Secs. 9 & 10.</p> <p style="text-align: right;">Var. 23° 30' E.</p>	
34.50	Spring branch and strip of timber, course S.W.	
40.00	<p>Set Basalt Stone 18 x 10 x 5 on S. side of Ridge for $\frac{1}{4}$ Sec. Cor.</p> <p>A Fir, 36 ins. in diam., bears N. 78° E., 112 lks., dist.</p> <p>No tree on W. side.</p>	
56.00	On Ridge, extends E. & W.	+800
80.00	<p>Set Basalt Stone 16 x 10 x 4 on N.W. side of Spur in mound of stone for Cor. to Sec. 3, 4, 9 & 10.</p>	-400