

## Township 3 N., R.37 E., W.M.

Chains			
10.00	Leave timber, course N.& S.		
40.24	Set Basalt Stone, 16 x 12 x 8 on S.E. face of Spur for $\frac{1}{4}$ Sec. Cor.		
43.00	On Spur; extends South.	+700	
80.48	The Cor. to Secs. 8, 9, 16 & 17 Land; Surface mountainous. Soil; 3rd rate. Some heavy timber in Gulch, mostly open ground. Good grass.	-250	
			Oct. 24, 1879.
	North between Secs. 8 & 9 . Var. 19° 30' E.		
8.00	On Spur, extends West	+150	
21.00	Enter timber, course N.&S.		
40.00	A fir, 8 ins. diam., on steep N. side of Spur for $\frac{1}{4}$ Sec. Cor. A fir, 11 ins. diam., bears S.36° E., 10 lks. dist. " " 6 " " " S.44° W., 16 " "		
42.00	Spring branch, course N.W.		
52.50	Brook, 10 lks. wide, course W.	-800	
57.00	Leave timber, course E.&W.		
80.00	Set Basalt Stone, 14 x 12 x 4 and post in mound of stone on steep S. face of Bluff for Cor. to Secs., 4, 5, 8 and 9. Land; surface mountainous. Soil: 3rd rate. Some heavy timber, fir, tamarack and pine. Good grass on open ground.	+700	