

Chains	timber, Fir, Tamarack & Pine. Good Grass on open ground	
	East on random line between Secs. 4 & 9. Var. 20°15' E.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.	
79.82	Intersected N.&S. line 88 lks. S. of Cor. to Secs. 3,4, 9 & 10, from which I run S.89° 22' W. on a true line between Sec. 4 & 9. Var. 21° 15' E.	
18.50	Brook, 8 lks. wide, course S.W.	-350
20.00	Leave timber. course N.E.& S.W.	
39.91	Set Basalt Stone 18 x 10 x 4 on steep S. slope for $\frac{1}{4}$ Sec. Cor. No trees.	
79.82	The Cor. to Secs. 4,5,8 & 9. Land; Surface mountainous. Soil, 3rd rate. Some good tim- ber, Tamarack, Fir and Pine. Good Grass.	+400
	North on a random line between Secs. 4 & 5. Var. 20° 15' E.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. Cor.	
79.84	Intersected N.Bdy. 120 lks. E. of Cor. to Sec. 4 & 5, from which, I run S 00° 51' E. on a true line between Sec.4 & 5. Var.	
	Theodore D.Romans house bears S.55° W. 250 lks.	
39.84	Set Willow post on level plateau for $\frac{1}{4}$ Sec. Cor. A Tamarack, 16 ins. in diam., bears N.34°E., 29 lks. dist. " " 15 " " " " N.26°W., 26 " "	
64.50	Leave timber, course E.&W.	-350
79.84	The Cor. to Secs. 4,5,8 & 9. Land; Surface, N. 64 chs. undulating plateau, S. 16 chs. steep mountain side. Soil; 3rd & 2nd rate. Heavy tim- ber, Fir, Tamarack, Spruce and Pine, some Willow and Alder underbrush.	-350
	Oct. 25, 1879.	