

Township 3 N., R. 37 E. W. M.

Chains	<p>marked and witnessed as described by the Surveyor-General, except that the marks on N.E. and S.E. witness trees have been obliterated; likewise the S.W. witness tree, a dead, badly decayed fir, has been defaced and</p>
	<p>A Fir, 12 ins. in diam. bears S.46°W., 36 lks. dist. marked T. 3 N., R. 37 E., S. 36, B. T. No tree in limit N.W.</p>
	<p>Land, level and mountainous. Soil, gravelly and stony; 3rd and 4th rates. Heavily timbered with pine, fir, tamarack, and spruce, 60.75 chs. Undergrowth, pine, fir, tamarack, spruce, alder, yellow maple, huckleberry, willow, thimbleberry, cascara, fern, elder and bunchgrass. Good pasturage. Mountainous, or heavily timbered land, 73.00 chs.</p>
	<p>July 26: At 2h.10m.P.M., l.m.t., I set off 45° 42' on the lat. arc; 19° 25' N. on the decl. arc and determine a true meridian by the solar at the Cor. of Secs. 25 & 36.</p>
	<p>Thence I run N. 1° 21' W., between Secs. 25 & 31.</p>
	<p>A long steep bank of stream, through heavy timber and undergrowth.</p>
5.00	Scattering timber; dense undergrowth.
7.50	Ravine-S.W.; ascend steep, grassy hill; bears N.W. & S.E.
12.85	The closing Cor. of Secs. 30 & 31.
	<p>Thence I run N. 0° 56' E., between Secs. 25 & 30.</p>
17.50	Top of point-W., descend into heavily timbered Ravine.
22.00	Foot; ascend grassy, stony hill, thru open timber; bears N.W. & S.E.
27.50	Gradual ascent thru heavy timber.
35.50	Top of hill; descend gradually.
40.00	A point 400 ft. above the Sec. Cor. and set a basalt Stone, 12 x 10 x 8 ins., 8 ins. in the ground, for $\frac{1}{4}$