

## Township 3 N., R. 37 E., W.M.

Chains	10°W.
80.00	<p>A point about level with the <math>\frac{1}{4}</math> Sec. Cor. and set an iron-stone, 20 x 8 x 4 ins., 15 ins. in the ground, for Cor. of Secs. 32 &amp; 33, marked with 4 notches on E. and 2 notches on W, edges, from which;</p> <p>A Fir, 14 ins. diam., bears N. 19 ° E., 1 ch. 69 lks. dist marked T.3 N., R.37 E., S. 33,B.T.</p> <p>A Fir, 16 ins. diam., bears N. ;9° W., 1 ch. 74 lks. distant, marked T.3 N., R.37 E., S.32,B.T.</p> <p>The old Cor. of Secs. 32 &amp; 33, a Basalt Stone, 14 x 10 x 5 ins., marked and witnessed as described by the Surveyor-General, bears N.89<math>\frac{1}{2}</math>°W., 1 ch.25 lks.dist, I destroy all traces of this old Sec. Cor.</p> <p>Land; level and mountainous.</p> <p>Soil; part arable, sandy loam, gravel and stone; 2nd &amp; 3rd &amp; 4th rates.</p> <p>Timber: pine, fir, tamarack and cottonwood.</p> <p>Undergrowth: pine, fir, tamarack, alder, willow, cottonwood, cherry, pinegrass, serviceberry and bunchgrass.</p> <p>Good pasturage.</p> <p>Mountainous, or heavily timbered land, 80.00 Chs.</p>
	August 9, 1900.
	<p>August 10: At 9 A.M., 1.m.t., I set off 45°41' 30" on the Lat.arc;15°55'30" N. on the Decl. Arc and determine a true meridian by the Solar at the Cor. of Secs. 32 and 33. Thence I run</p> <p>N.89°44' W., on a true line, S. Bdy. of Sec. 32.</p> <p>Ascending steep, grassy bank, thru scattering timber &amp; undergrowth;bears N.&amp; S.</p> <p>2.50 Top of point-S.30°E., descend; bears N.70°W. and S.70°E.</p> <p>11.25 Leave timber on point-S.;steeper descent into canyon, bears N.30°W. and S.30°E.</p> <p>18.75 Foot; boulder bed.</p> <p>19.15 Branch of River, 10lks.wide, runs S.30° E. over bed rock bottom; thence ascend over steep bluffs, through timber and dense unfergrowth;bears N.40°W. and S.40°E.</p>