

Township 3 N., R. 37 E., W.M.

Chains	From the Cor. of T.3 N., Rs. 36 & 37 E., before described, I run
	N., between Secs. 31 & 36.
	Over rolling, alluvial land, through heavy timber and dense undergrowth.
33.00	Leave dense undergrowth of swampy ground and cross small stony prairie with scattering timber.
37.60	Stock trail; bears N.80° W. and S. 80° E.
39.50	Descend over N. brow of mountain.
40.00	A point about level with Tp. Cor. and set a Basalt Stone, 15 x 10 x 4 ins. 10 ins. in ground for $\frac{1}{4}$ Sec. Cor., W. Bdy. of Sec. 31, marked $\frac{1}{4}$ on E. face, from which A fir, 32 ins. diam., bears N.80° E., 15 lks. dist. marked $\frac{1}{4}$ S.31, B.T. Thence through heavy timber; bears E.&W.
40.64	A point 50 ft. below the last Cor. and set a Basalt Stone, 24 x 12 x 4 ins., 18 ins. in the ground, for $\frac{1}{4}$ Sec. Cor., E. Bdy. of Sec. 36, marked $\frac{1}{4}$ on W. face, from which the original A fir, 10 ins. diam., bears N. 10° W., 50 lks. dist. marked $\frac{1}{4}$ S., B.T. I obliterate the marks on A fir, 20 ins. diam., bears S.40° E., 21 lks. dist. Thence I run
	N. 1° 42' W., through heavy timber and undergrowth.
57.00	Deep Ravine, course N.W.; ascend stony, grassy hillside through scattering timber and undergrowth.
80.00	A point 400 ft. below the $\frac{1}{4}$ Sec. Cor., W. Bdy. of Sec. 31, near the top of Ridge and set a Basalt Stone, 15 x 12