

Township 3 N., R.37 E., W.M.

Chains	<p>No tree in limit N.E. and I raise a mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, E. of Cor. Pits impracticable.</p> <p>Land; mountainous.</p> <p>Soil; gravelly and stony; 3rd & 4th rates.</p> <p>Timber; pine, fir and tamarack.</p> <p>Undergrowth; pine, fir, tamarack, alder, willow, cascara, cherry and bunchgrass.</p> <p style="text-align: right;">August 28, 1900.</p>
1.35	<p>North between Secs. 19 & 25.</p> <p>Ascending grassy hillside through scattering timber; bears N.20° W and S.20° E.</p> <p>The Cor. of Secs. 24 & 25, before noted as partially defaced; I reestablish by setting a Basalt Stone, 24 x 12 x 3 ins., 18 ins. in ground, for Cor. of Secs. 24 & 25, marked with 4 notches on N. and 2 notches on S. edges, and raise a mound of stone, 2 ft. base, $1\frac{1}{2}$ ft. high, W. of Cor. Pits impracticable.</p> <p>Thence N. on blank line, E. Bdy. of Sec. 24; at 38.65 chs. set temporary $\frac{1}{4}$ Sec. Cor., W. Bdy. of Sec. 19; at 40.00 chs. fail to find any trace of the old $\frac{1}{4}$ Sec. Cor., E. Bdy. of Sec. 24; set temporary Cor. and at 75.00 chs. intersect the Cor. of Secs. 19 & 24, and set a post on summit of ridge, marked and witnessed as described by the Surveyor-General.</p> <p>North, between Secs. 19 & 24, counting distance from closing Sec. Cor..</p> <p>10.00 Point-N.W.; descend.</p> <p>11.25 Steep descent through timber and dense undergrowth; bears E.&W.</p> <p>17.85 Ravine, course N.W.; ascend open, grassy point.</p> <p>19.25 Scattering timber and undergrowth; slope S.80° W.</p> <p>31.75 Trail on ridge; bears N.W. & S.E., descend through heavy timber and dense undergrowth.</p> <p>40.00 A point 500 ft. below the closing Sec. Cor., and the temp. $\frac{1}{4}$ Sec. Cor.</p> <p style="text-align: right;">A fir, 5 ins. diam., for $\frac{1}{4}$ Sec. Cor., W. Bdy. of</p>